## MYSORE RAILWAYS.

### MYSORE DIVISION (OPEN LINES).

*Notification dated 1st February* 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Open Line Division, Mysore Railways, Mysore, up to 4 P.M., on Friday the 26th February 1932, from Contractors, who are willing to do the work of construction of a room for storing waste in Central Stores, Mysore.

2. Every tender must be accompanied by an earnest money or Rs. 200 which can be paid to the Auditor, Mysore Railways, Mysore, and the receipt thereof enclosed along with the tender.

3. Tenders should be submitted in special forms, which can be obtained from the Executive Engineer, Mysore Railways, Mysore, on payment of Rupee one.

4. Tenders which give rates, as per estimate rates or so much per cent, above or below estimate rates will not be considered.

5. The name of the accepted tenderer will be posted on the Notice Board of the Executive Engineer's Office, by 7th March 1932. No enquires regarding the acceptance or rejection of a tender will be replied.

6. The earnest money of the unsuccessful tenderers will be returned as soon as possible after the tenders are disposed of, while that of the successful tenderer will be accepted as part payment towards the security deposit due as per para 7 *infra*.

7. The successful tenderer should deposit with the Auditor, Mysore Railways, Mysore, before they sign the schedule agreement 5 per cent of the value of the work for which the tender is accepted as security for due fulfiment of the terms of the agreement.

8. The final acceptance of the tender will rest with the Superintendent, Way and Works, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves to himself the right to reject, without assigning any reasons therefor, any or all the tenders.

9. Work should be started within two weeks, from the date of acceptance of tender and completed before 10th June 1932, with a guaranteed monthly rate of progress. The accompanying schedule gives the approximate quantity of works and this quantity is not guaranteed.

10. The time limit specified in para 9 should be strictly adhered to and any violation of this will render the contractor liable to forfeit his 5 per cent deposit amount not as a penalty but as ascertained and liquidated damages recoverable accordingly.

11. Plans and specifications and other details of work to be done are available for inspection in the Executive Engineer's Office, Mysore Railways, Mysore, where intending tenderers may call and obtain required information during office hours.

12. In all matters of dispute regarding rates, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintendent, Way and Works, Mysore Railways, will be final and legally binding.

SCHEDULE.

| Sl. No. | Particulars | Per | Quantity |
|---|---|---|---|
| 1 | Earthwork excavation and filling in basement | C.ft. 1.000 | 995 |
| 2 | Concrete in sand mortar | 100 C.ft. | 445 |
| 3 | Burnt brick in sand mortar | 100 C.ft. | 1,860 |
| 4 | Burnt brick in mud | 100 C.ft. | 1,000 |
| 5 | Burnt stone slabs 6" thick roughly dressed | S.ft. | 185 |
| 6 | Drilling holes in slabs | Each | 18 |
| 7 | Cutting, hoisting and fixing 41¼ lbs. rails supplied departmentally. | R.ft. | 93 |
| 8 | Preparing, hoisting and fixing steel trusses for 20′ span supplied departmentally and assembling complete with bolts and nuts. | Each | 2 |
| 9 | Preparing, hoisting and fixing T. Iron steel verandah rafters and iron purlins and cleats including drilling holes (materials to be supplied departmentally). | Cwt. | 21·30 |
| 10 | Fixing G. I. Sheets on roof inclusive of ridging and wind ties supplied departmentally complete). | Sqr. | 13·30 |
| 11 | Preparing and fixing C. I. Sheet door with iron frame (2½" x 2½" x 3/8") with flat iron hinges and locking arrangements complete (materials to be supplied departmentally.) | S.ft. | 34 |
| 12 | Preparing and fixing C. I. Sheet windows with angle iron | | |

| Sl. No. | Particulars | Per | Quantity |
|---|---|---|---|
| 13 | Preparing and fixing iron Ventilators with wire gauze shutters and bars complete (materials to be supplied departmentally). | S.ft. | 60 |
| 14 | Preparing and fixing sun shades and windows over ventilators of angle iron frames and C. I. Sheet covering and complete with cross bolts and nuts (materials to be supplied departmentally). | Each | 11 |
| 15 | Chunam plastering .. ... | Sqr. | 30·40 |
| 16 | White and colour washing ... ... | ,, | 30·40 |
| 17 | Chunnam borders 9″ x 9″ ... ... | R.ft. | 76 |
| 18 | Bending and fixing 41¼ lbs. Fish plates (supplied departmentally). | Each | 12 |
| 19 | Flooring with 4″ burnt stone slabs, one line dressed over 3″ concrete bed including cement pointing. | Sqr. | 8·30 |
| 20 | Painting with silicate chocolate paint, 2 coats ... | ,, | 10 |
| 21 | Earthwork ramps all round buildings and filling in basement and hollows here and there and widening bank including lead of 1,000 R.ft. | 1,000 C.ft. | 12,800 |
| 22 | Cleaning site .. ... | Lump | sum |

R. N. MIRZA,
*Senior Executive Engineer.*

## HASSAN DIVISION.

### FORM OF ADVERTISEMENT.

*Notice dated 31st January 1932.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 15th February 1932, for making additions and alterations required to Government Middle School at Arsikere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred only (Rs. 100) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for making additions and alterations to the Government Middle School at Arsikere, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for making additions and alterations required to the Government Middle School at Arsikere.

| Sl. No. | Name of work | Unit | Quantity |
|---|---|---|---|
| 1 | Removing the existing roof with reepers and rafters and tiles complete and stacking, | Sqr. | 14·46 |
| 2 | Dismantling brick masonry .. ... | C.ft. | 308 |
| 3 | Removing old door and windows and repairing them including fixing in new wall. | Each | 5 |
| 4 | Earthwork excavation for foundation and filling in basement. | Cyd. | 24 |
| 5 | Size stone in clay ... .. ... | C.ft. | 1084 |
| 6 | Burnt brick in clay .. .. .. | ,, | 13·48 |
| 7 | Do in mortar .. .. | ,, | 518 |
| 8 | Do arch work .. .. ... | ,, | 64 |
| 9 | Burnt stone slabs 5 to 6″ thick dressed and fixed ... | S.ft. | 253 |
| 10 | Removing and Refixing slabs .. .. | ,, | 77 |
| 11 | Teak wood windows half glazed and half battened shutters in four halves with ¾″ iron bars fitting, etc., complete | ,, | 48 |
| 12 | Teakwood Almira frames with panel shutters and cross planks for wallshelves including fittings. | ,, | 39 |
| 13 | Teakwood circular glazed ventilators .. | ,, | 14 |
| 14 | Cement concrete perforated ventilator including carriage and fixing. | ,, | 48 |
| 15 | Dismantling wall and fixing rectangular ventilators with the required masonry etc., complete. | Each | 4 |
| 16 | Making holes in walls for inserting joists and fixing .. | Each | 15 |
| 17 | Teakwood work wrought and put up including wood oiling and tarring. | C.ft. | 125·84 |
| 18 | Dormon Long & Co., rolled steel girders including Railway freight, hoisting, painting and fixing. | Cwt. | 8·00 |
| 19 | Roofing with 1st class Mangalore tiles in teak reepers .. | Sqrs. | 4·30 |
| 20 | Roofing with available old materials and fresh reepers wherever necessary. | Sqrs. | 13·00 |
| 21 | Ridge tiles set in mortar .. ... | R.ft. | 64 |
| 22 | Roofing with pucca terrace with plastering, etc., complete... | Sqr. | 3·80 |
| 23 | Plain parapet wall as per details .. ... | R.ft. | 18 |
| 24 | Cornice 6″ thick complete ... ... | ,, | 18 |
| 25 | Zinc water spouts ... ... ... | Each | 2 |
| 26 | Teakwood plank ¾″ for valleys ... .. | S.ft. | 105 |
| 27 | Plain zinc sheet valleys .. .. | ,, | 105 |
| 28 | Cement mortar bands and pointing 3′ wide ... | R.ft. | 35 |
| 29 | Do do over gables ... ... | ,, | 46 |
| 30 | Plastering with mortar ... ... | Sqr. | 29·47 |
| 31 | Cement pointing ... ... ... | ,, | 1·85 |
| 32 | White washing ... ... ... | ,, | 31·55 |
| 33 | Flooring with Cudappah slabs on 3″ concrete bed and cement pointing. | ,, | 4·65 |
| 34 | Chacolate painting ... .. .. | ,, | 4·33 |

M. A. SRINIVASACHARI,
*Executive Engineer.*